


Massachusetts Water Resources Authority

2021 Water Use Trends and Reservoir Status


February 16, 2022



Total Consumption by MWRA Communities (1980 to 2021)











Boston Water Use (1900 to 2021)






Boston's Share of Total Demand






Fully Supplied Communities Demand (2000 to 2021)






Fully Supplied Communities (Annual Base and Outdoor Use)






Reservoir Withdrawals – 5 Year Running Average





Quabbin Reservoir Volumes for 2020 to 2021





Massachusetts Water Resources Authority

Metropolitan Redundancy Interim Improvements Projects Update

February 16, 2022



Commonwealth Avenue Pumping Station



- Provides redundancy for City of Newton if City Tunnel taken out of service
- Alternate low service supply from WASMS 1 and 2
- New low service pumps



New Low Service Pumps 4 and 5






New Service Line Connection to Low Service WASM 1 and 2





Low Service Pressure Reducing Valve Improvements



- Increase capacity of WASM high service supply to Northern Low System
- Low service pump stations can supply Northern High Service in event of a tunnel failure

Existing PRV Vaults





W16 Mystic Valley Parkway PRV Vault

W14 Nonantum Road PRV Vault




Construction of New Nonantum Road PRV Vault





Top of Shafts 6, 8 and 9A Interim Improvements



Contract 7561 improved and protected critical facilities related to the existing tunnel system at:

Shaft 6 - Newton

Shaft 8 – Brighton

Shaft 9A - Malden

Future work at:

Shaft 5 – Weston

Shaft 7 – Boston College

Shaft 7B - Chestnut Hill

Shaft 7C – Dorchester

Shaft 7D – Dorchester

Shaft 9 – Somerville




Shaft 8 Before and After Epoxy Coating





Shaft 9A Air Valve – Before And After Encapsulating Coupling (installed by MWRA)







Carbon Fiber and Wax Tape Wrap Complete








Rehabilitation of WASM 3 (Medford, Somerville and Arlington)

MWRA Weston Aqueduct Supply Main - CP1 Rehabilitation





WASM3 - Existing Pipe, Cleaned Pipe, New Cement Lining










WASM 3 - Cement Lining Machine and Conveying Machine








WASM 3 – New Air Valve Structure





WASM 3- Access Pits Over 60-inch Pipeline







Chestnut Hill Pump Station Design



- New connection to provide isolation of pumping station in the event of failure of the City or Dorchester Tunnels
- Allows pumping from Chestnut Hill Reservoir to Southern High and Southern Extra High service areas in emergency




Massachusetts Water Resources Authority

Northern Extra High Pressure Zone Improvements Section 63 (Lexington) Contract 6522

February 16, 2022

Project Schematic





Contract 6522 Bid Results


Bidders	Bid Amount
Engineer's Estimate	\$9,625,000
GVC Construction, Inc.	\$10,919,410*
Albanese, D&S, Inc.	\$11,737,000
R. Zoppo, Corp.	\$12,596,500
RJV Construction Corp.	\$12,632,500
Revoli Construction Co. Inc.	\$12,952,500



Massachusetts Water Resources Authority









FY22 Target for FTEs = 1150

FTEs as of December 2021 = 1,090.7


Tunnel Redundancy as of December 2021 = 10



Q2-FY22 there were three blow off valves replaced. The total replaced for the fiscal year to date is three. Below target due to isolation and permit issues and staff vacancies.




The Percent On-Time measurement fell below the 95% goal due to staffing vacancies






Energy Costs - Deer Island








Clinton Wastewater Treatment Plant Flow





Reservoir Water Quality






Distribution System Water Quality

Chlorine Residuals in Fully Served Communities

	2020 2021												
	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
% < 0.1	0.1	0.0	0.0	0.0	0.0	0.0	0.1	0.3	0.3	0.7	0.9	0.5	0.4
% < 0.2	0.4	0.2	0.1	0.0	0.0	0.0	0.2	0.7	1.3	2.8	3.1	1.7	0.8
% < 0.5	2.5	1.9	8.0	0.2	0.3	0.2	0.6	2.6	6.0	12.3	10.9	7.4	2.8
% <1.0	5.3	3.6	2.5	1.5	2.0	1.0	2.1	8.6	17.3	27.9	26.2	15.7	7.3
% <u>></u> 1.0	94.7	96.5	97.6	98.5	98.0	99.0	97.9	91.4	82.7	72.1	73.8	84.4	92.7

Monthly Total Coliform Positives





Massachusetts Water Resources Authority

MWRA Fiscal Year 2023 Proposed Current Expense Budget


February 16, 2022



FY23 Proposed CEB Budget Structure – Direct Expenses

Direct Expenses by Category

(\$s in millions)






FY23 Proposed CEB Budget Structure – Indirect Expenses

Indirect Expenses by Category

(\$s in millions)






FY23 Proposed CEB Budget Structure – Capital Finance Expenses


Capital Financing by Category

(\$s in millions)






FY23 Proposed CEB Budget Structure – Non-Rate Revenue





FY23 Proposed CEB - Rate Projections (Combined Utilities)


MWRA Combined Utilities Historical and Projected Rate Revenue Changes





FY23 Proposed CEB - Rate Projections (By Utility)

MWRA Water & Sewer Utilities Historical and Projected Rate Revenue Changes





Massachusetts Water Resources Authority

Proposed Amendments to Management Policies

February 16, 2022



Proposed Amendments to Management Policies

Category	Delegate	Current Delegation	Proposed Delegation
Purchasing	Executive Director	\$1,000,000	\$3,500,000
	Director of Administration	\$35,000	\$120,000
	Director of Procurement	\$25,000	\$90,000
	Purchasing Manager	\$5,000	\$20,000
	Authorized Representative	\$2,000	\$10,000
Purchasing Amendments	Executive Director	25% of original contract or \$250,000 and not more than 6 months.	25% of original contract and not more than 6 months.
Chemical Purchases	Executive Director	N/A	\$15,000,000
Construction Contracts	Executive Director	\$1,000,000	\$3,500,000
Change Orders	Executive Director	25% of original contract or \$250,000 and not more than 6 months.	25% of original contract or not more than \$1,000,000 and not more than 6 months.
Professional Services (With an Individual)	Executive Director	\$50,000 and 12 months	\$200,000 and 24 months
Professional Services (With a Firm)	Executive Director	\$100,000 and 12 months	\$1,000,000 and 36 months
Non-Professional Services	Executive Director	\$250,000	\$1,000,000
Professional and Non- Professional Services	Director of Administration and Chief Operating Officer	\$35,000 and 12 months	\$350,000 and 12 months
	Deputy Chief Operating Officer, Director of Finance and General Counsel	\$10,000 and 12 months	\$100,000 and 12 months
	Authorized Designee	\$5,000 and 12 months	\$50,000 and 12 months
Amendments	Executive Director	25% of original contract or \$250,000 and not more than 6 months.	25% or \$500,000 and not more than 12 months. Re- delegation from the Board consistent with Change Orders
Temporary Delegation of Authority (All Categories)	A designee duly authorized in writing by the Executive Director		All approvals delegated to the Executive Director

Other Proposed Changes:

Human Resources

- Board only approves appointment of non-union staff
- PCR Amendments for title or cost center under Executive Director's delegated authority

Law

 Approval of claims under Executive Director's delegated authority increased from \$100,000 to \$300,000



Massachusetts Water Resources Authority


CSO Post-Construction Monitoring and Performance Assessment Contract 7572, Amendment 3

February 16, 2022




Long-Term CSO Control Plan

- CSO annual discharge volumes
 - Down to 87% of 1988 levels
 - Reduced by 2.8 billion gallons
 - 93% treated
- Completed 35 projects/184 Milestones
- Total program cost \$911M
- Final Performance Assessment report
- Demonstrated water quality Improvements
- Future Challenges



- Assessment of program achievements:
 - Documentation of system improvements
 - Hydraulic model update to determine outfall performance
 - Receiving water models to understand water quality improvements
- Support development of required reports
- System optimization evaluations to support variances





Proposed Amendment

3 year extension to:

- Updated CSO Control Plan (variance requirement)
- Program Support
- Additional Investigations and Tracking of 16 CSO Outfalls
- Assist with Annual Progress Reports
- Assist with Supplement to Final Report

